





MAGNETO-WHAT? Lessons Learned from Design & Construction of Mayo Clinic's Magnetoencephalography (MEG) Lab

- LEARNING OBJECTIVES
- 2 TEAM INTRODUCTION
- WHAT IS MAGNETOENCEPHALOGRAPHY?
- 4 PRE-DESIGN THROUGH CONSTRUCTION
- 5 PROJECT PHOTOGRAPHY
- 6 Q&A



# LEARNING OBJECTIVES

# LEARNING OBJECTIVES

### DEFINE

 The diagnostic and treatment functions of MEG equipment

### IDENTIFY

 The appropriate sites, delivery paths, and staging areas for a MEG Lab based on vendor requirements

### **EVALUATE**

The programmatic
 elements and engineering
 considerations for a MEG Lab

# TEAM INTRODUCTIONS

# PRESENTATION TEAM




ERIC STRICKLAND

Senior Healthcare Planner
RSP Architects



Professor of Neurology and Associate Professor of Biomedical Engineering Mayo Clinic



CHARLES ASAMOAH, P.E.

Project Manager

Department of Facilities

Project Services

Mayo Clinic



CRAIG NEUSER

Construction Manager
Department of Facilities
Project Services
Mayo Clinic

# PROJECT TEAM

### Design Team

- RSP Architects Architecture & Interior Design
- Design Engineers Mechanical, Electrical And Plumbing Engineer
- MBJ Structural Engineer

### **Equipment Vendors**

- Megin Magnetoencephalography (MEG) Equipment Vendor
- Vacuumschmelze (VAC) Magnetically Shielded Room Vendor

#### General Contractor

• Benike Construction



# WHAT IS MAGNETOENCEPHALOGRAPHY (MEG)?

# WHAT IS MEG?


- A technician can measure the magnetic fields that arise from neuronal activity in the brain.
- MEG does not use any magnets. Rather, the test uses very sensitive detectors to measure magnetic fields from the brain.
- The MEG test takes place in a room built to block external magnetic fields.
- During MEG, a patient sits or lies on their back without moving. Sensors in the helmet record magnetic activity in the brain.



# WHAT IS MEG?


#### **Indications**

- Epilepsy Pre-surgical evaluation in patients with intractable focal epilepsy to identify and localize area(s) of epileptiform activity.
- Mapping Functional Brain Areas Pre-surgical brain mapping to identify, localize and preserve eloquent cortex before resective surgery (tumors and vascular malformations, epilepsy)
- MEG is not a stand-alone test for epilepsy. A comprehensive evaluation is necessary, in context with other presurgical tests
- MEG cannot replace, but may guide the placement of intracranial EEG



### Clinical MEG Locations


ACMEGS Center Member MEG sites by state. Send corrections to info@acmegs.org




Source: <a href="https://www.acmegs.org/center-directory/">https://www.acmegs.org/center-directory/</a>

# PRE-DESIGN


# PRE-DESIGN SITE VISIT -UT SOUTHWESTERN MEDICAL CENTER












# PRE-DESIGN SITE VISIT - CLEVELAND CLINIC



Workstations Office

**EEG Prep and Charting** 

MEG Unit and Shielded Room

Control Desk Helium Tanks









# VENDOR DESIGN RESOURCES

#### TRIUX™ neo

Site Design and Construction Guide

Document ID: Publication date: Language: NM21643A-E1 April 2022 English

**MEGIN** 



October 1, 2018

#### TRIUX™ neo site selection

Maintain the following minimum distances to sources of magnetic and radiofrequency noise:

- Trains, trams, metro lines: >150 meters (500 ft)
- Driveways and parking: >15-20 meters (50-65 ft)
- Elevators: >15-20 meters (50-65 ft)
- WiFi transmitters: >10 meters (35 ft)
- Large moving metal objects: >10 meters (35 ft)
- High-voltage power lines: >15–20 meters (50–65 ft)
- 1.5 T MRI scanners: >10 meters (35 ft) with gantry perpendicular to the MRI bore

#### Space requirements

- Minimum laboratory space: 50 m² (540 sq ft)
- Recommended laboratory space: 70 m² (750 sq ft)
- Floor load carrying capacity: >500 kg/m² (100 lb/sq ft)
- Free height of the area for MSR: >3 meters (10 ft)
- Access to the site: >100 cm x 200 cm (3.3 x 6.6 ft) (w x h)

#### Required infrastructure:

- Electrical installation (see power requirements in datasheet)
- Connection to hospital IT network
- Internet connection (https) for remote support
- Data storage for measurement files on hospital server

 $MEGIN \ | \ Elekta\ Oy\ | \ Siltasaarenkatu\ 18-20, FI-00531\ Helsinki, FINLAND\ | \ Tel.\ +358-9-756\ 2400\ | \ Fax\ +358-9-756\ 24011$ 



# Magnetic Shielding Room Preparation Guidelines

VACUUMSCHMELZE GmbH & Co KG

Materials and Parts Division

Grüner Weg 37

63450 Hanau

Germany

www.vacuumschmelze.com

All rights reserved. Reproduction in any form without the written permission of VAC is strictly prohibited.

#### NOTICE

This document contains copyrighted and possibly confidential information and is intended for the exclusive use of customers planning to purchase a MSR by Vacuumschmelze GmbH & Co KG

Disclosure to others or is strictly prohibited without the written authorization of VAC

VAC reserves the right to make changes in the specifications or data shown herein at any time without notice or obligation.

VAC denies any responsibility for damage to apparatus or persons due to improper use or service performed by unauthorized persons.

VAC assumes no liability for damage and/or failure of equipment caused by faulty site preparation.

information

.

# PROGRAMMING

# PROGRAMMING -MEGIN ELEMENTS

### Vendor Program Elements

- Operator Area
- Magnetically Shielded Room (Provided by VAC)
- Two (2) Technical Areas
- Shower/Changing Area/Toilet
- Storage Room

#### 5 Designing MEG laboratory layout




Figure 5.2 Layout example of an MEG laboratory

Source: NM21643A-E1\_TRIUX\_neo\_SDCG\_Release candidate\_2022-04-13.pdf

# PROGRAMMING – VAC MAGNETICALLY SHIELDED ROOM

### Magnetically Shielded Room (MSR)

- Outside dimensions:
  - o 14'-9 34" × 11'-6"W × 9'-5"H
- Inside dimensions:
  - o 12'-11 ½"L x 9'-7 5/8"W x 7'-10 ½"H
- Level entry is preferred. Recessed pit dimensions:
  - o 14'-11"L x 11'-7 34"W x 9"D
- Required minimum room height (without pit):
  - 0 9'-6"



Each MSR is being tested on site after its setup following our test guideline and the achieved performance is filed in a test report which will be handed over.

#### 2.2. Dimensions

The following table refers to our standard type VACOSHIELD ADVANCED (Ak3b) with 3x4m² and two layers of MUMETALL®.


Multilayer solutions and additional standard sizes are available like 2,5x2,5 m<sup>2</sup> and 4x5 m<sup>2</sup>. Customized solutions are possible as well.

	length	width	Height
Inside Mumetall surface	4.008 m 13'-2"	2.999 m 9'-10"	2.480 m <sup>8'-1 5/8"</sup>
Inside decoration surface	3.946 m 12'-11 1/2"	2.937 m <sup>9'-7 5/8"</sup>	2.400 m <sup>7'-10 1/2"</sup>
Outside Mumetall surface	4.355 m 4.355 m	3.345 m 3.344"	2.850 m <sup>9'-4 1/4"</sup>
Outside decoration surface	4.513 m <sup>-9 3/4</sup> "	3.503 m 3.503 m	2.870 m <sup>9'-5"</sup>
Pit for standard door	4,55 m (min)	3,55 m (min)	115mm (max)
Pit for level entry door	4,55 m (min)	3,55 m (min)	236mm (max)

#### 2.3. Assembly possibilities

WALL INICKN	IESS - INTERIOR	WALL IMICKN	ESS - EXTERIOR
13'-2"	9'-10"	14'-9 3/4"	11'-6"
12'-11 1/2"	9'-7 1/2"	14'-3 1/2"	10'-11 3/4"
0'-2 1/2"	0'-2 1/2"	0'-6 1/4"	0'-6 1/4"

WALL THICKNESS INTEDIOR WALL THICKNESS EXTERIOR




1. Free Standing – minimum 60 cm around 3 sides, min. 2 m on the door wall. **Required minimum room height 2.9 meters** 

9'-

Source: MSR Preparation Guideline Advanced 3x4 - LB.pdf

# PROGRAMMING – PROGRAM AND DIAGRAMS





| DRESSING | 41 46 SF | (42.00 SF) | (22.00 SF) | (22.00

BLOCKING DIAGRAM 'B'

BLOCKING DIAGRAM 'A



#### SPACE PROGRAM

Prepared by Division of Architectural and Engineering Services

Project: Magnetoencephalography Project # ROXX22C0170
Date: 12 October 2022

Revisions:

Prepared By: RSP Architects

_		_			_				
		_	DEOLUC	TEED	PROPOSED				
Н		$\vdash$	REQUES' NSF	NSF	$\vdash$	NSF	NSF		
#	FUNCTION/AREA	#	AREA	TOTAL	#	AREA	TOTAL	MMENTS	
1	FONCTIONAREA	"	AKLA	TOTAL	"	AKEA	TOTAL	AVENUENTS	
2	Public Areas	$\vdash$			$\vdash$				
3	Reception/Check-In	1	100	100	$\vdash$			uld share ev	isting reception with another department
4	Waiting Room	1	120	120	$\vdash$				isting waiting room with another department
5	Public Toilet/s	1	56	56	$\vdash$				sting public toilet/s with another department
6	Subtotal Public Spaces (NSF)	Ť.	30	276	$\vdash$			uu siiare exi	sting paone tonces with another department
7	Subtotal Fublic Spaces (1451)			270	$\vdash$				
8	MEG Laboratory	$\vdash$			$\vdash$				
9	Desk Operations Specialist (DOS)	1	56	56	$\vdash$				
10	Sub-Wait	1	90	90	$\vdash$			hairs x 15 N	ISF/chair
11	Dressing Room	1	42	42	$\vdash$				ce Standard E2034.03.01-16
12	Patient Toilet	1	56	56	$\vdash$				ce Standard RS 1021.02.01-10
13	Analysis Work Station	4	56	224	$\vdash$			2	v, 1 staff, 1 other in shared worked area
14	Patient Prep Area	1	100	100	$\vdash$				k, hair-wash sink, cap wash sink,drying space;3D digi-chair
15	Magnetically Shielded Room (MSR)	1	180	180	$\vdash$			o-layer MS	
16	Equipment Room A (adjacent to MSR)	1	108	108	$\vdash$				er cabinet, electronics cabinet
17	Equipment Room B (reqd dist from MSR)	1	120	120	Н				ycler,cryocooler compressor,air compressor,MEG servers
18	Storage Room	1	100	100	Н				sfer dewar,siphons,He transfer tools,safety devices,cyrokit
19	Subtotal MSR Laboratory (NSF)			1,076	г				
20				3,070	Н				
21	Building Support	$\vdash$			$\vdash$				
22	Electrical Room	0	120	0	Г				
23	Point of Presence Room	0	126	0	Г			G servers v	vill be located in MEG Lab
24	Environmental Services Room	0	200	0				t required p	er Mayo EVS
25	Subtotal Building Support(NSF)			0	Г				
26					Г				
27					Г				
28					Г				
29									
30									
31									
32									
33									
34									
35									
36									
37									
38									
39									
40									
41									
42	Total net square feet (NSF)			1,352					
43	Net to Gross Factor			1.3					
44	Department Gross Square Feet (DGSF)			1,758					

10/12/2022 Pagel Magnetoencephalography/ROXX22C0170\_Space Program.xlsx

### PROGRAMMING - SITE ANALYSIS

#### ALFRED BUILDING, THIRD LEVEL

Year Built: Original drawings are dated 1964

Structural System: Cast-in-place concrete pan and joist system supported by concrete beams and


concrete columns

Floor-to-Floor height: 12'-0"

Floor to bottom of structure height: 10'-4" below the concrete joists and concrete beams.

Concrete beams and joists are the same depth

**Floor Live Load Capacity:** Past structural calculations for the existing floor structure indicate the steel reinforcing used in the concrete is undersized for the existing 3" deep non-structural topping slab. The dead load of the topping slab reduces the floor live load capacity to approximately 50 PSF.



(Alfred 03 - Site Observations for Potential MEG Location, 12/05/2022)

#### JOSEPH BUILDING, FOURTH LEVEL

Year Built: Original drawings are dated 1920

**Structural System:** Cast-in-place concrete pan and joist system supported by concrete beams and


concrete columns

Floor to Floor Height: 12'-0"

Floor to Bottom of Structure Height: Varies from 10'-11" below the concrete joists to 9'-5" below

concrete beam

**Load Capacity of Floor:** The building was originally a bed tower with surgical suites on the upper floors. The original Floor Live Load capacity in the patient room areas was 40 PSF.



(Joseph 04 - Site Observations for Potential MEG Location, 12/05/2022)


#### DOMITILLLA BUILDING, MAIN LEVEL

Year Built: Original drawings are dated 1954


**Structural System:** Cast-in-place concrete with the Main Level area of consideration a concrete slab-on-grade. Floor structure above is a flat concrete slab supported by concrete beams and concrete columns.


Floor to Floor Height: 11'-9"

**Floor to bottom of flat slab:** 11'-3" to bottom of slab and 9'-5" to bottom of concrete beams **Floor load capacity:** The Main Level concrete slab-on-grade in the area of consideration could support 100 PSF or more with some additional investigation required.




(Domitilla Main Floor - Site Observations for Potential MEG Location, 11/16/2022)






# PROGRAMMING - PROJECT LOCATION

# SCHEMATIC DESIGN






SCHEMATIC DESIGN-BUILDING SECTION

# DESIGN DEVELOPMENT

# DESIGN DEVELOPMENT





## DESIGN DEVELOPMENT

The block diagram shows the main modules in the MEG system used for signals and control electronics.




Figure 3.4 Block diagram of the MEG system

The probe unit is the main part of the MEG system and it is located in the MSR.

The MSR protects the probe unit inside the MSR and the MEG SQUID sensors inside the probe unit from environmental disturbance. The MEG SQUID signal cables, the EEG signal cables and the control cables entering the MSR are isolated to eliminate noise from penetrating the MSR and to maintain a low environmental noise level for measurements inside the MSR.

The noise isolation for the signal, power and control cables takes place in the filter cabinet. The filter cabinet is connected to electronics cabinet. The electronics network in the electronics cabinet is connected to a switch and further with optical fibers to MEGLAB network switch.




Figure 3.15 Helium emergency exhaust duct

For more information, see the dimensional drawing for the tube which the customer needs to Appendix A *Helium emergency exhaust design*.




Figure 5.1 Helium recycler modules and cables

- (1) Cryocooler cold head
- (2) Probe unit
- (3) Helium gas lines
- 4) Helium recycler cabinet
- (5) Helium gas storage tanks
- 6) Cryocooler gas lines
- (7) Cryocooler compressor
- 8) Cryocooler compressor control and power cables (through the filter cabinet)
- 9) Measurement workstation
- (10) Magnetically shielded room (MSR)
- (11) Cryocooler filtered side power cable
- (12) Cryocooler shielded side thermometer cable
- (13) Control cables between the helium recycler cabinet and filter cabinet
- (14) Cryocooler unshielded side power cable
- (15) Cryocooler control interface cable set
- (16) Helium gas line
- (20) Cryocooler gas line
- (21) Cryocooler gas line
- (22) MEGLAB network switch using VLAN meg.lab.

# CONSTRUCTION DOCUMENTS


# CONSTRUCTION DOCUMENTS


### Mechanical & Electrical Challenges


- 40% relative humidity
- No rotating equipment near Equip Room or MSR
- Tight space between ceiling and structure above
- Existing Comm Room not large enough for MEG Lab comm

### Mechanical & Electrical Solutions

- 4 mil vapor in MEG Lab perimeter and humidifiers in adjacent Mech Room
- VAVs in adjacent Mech Room instead of FCU in Equip Room
- Converted an existing Toilet Room into a Comm Room







Architectural Equipment Plan

Megin Site-Specific Equipment Installation Plan


# CONSTRUCTION DOCUMENTS - EQUIPMENT COORDINATION

### Occupancy Classification – Challenges

- Originally an I-2 Occupancy Building with inpatient bedrooms but had been converted to a B occupancy
- Occasional Neurology inpatient treatments in MEG suite required conversion back to I-2

### Occupancy Classification – **Solutions**


 Collaborative effort between Mayo, Intertec, and Construction Team to inspect all rated doors, penetrations, and rated caulking in life safety walls




# CONSTRUCTION DOCUMENTS - LIFE SAFETY AND CODE REVIEW

### Equipment Delivery - Challenges

- Coordination with overseas shipping
- Coordination between Mayo Clinic, VAC, and Beltmann Transportation
- Distance from loading dock to project site
- Equipment weight of 1200 5300 pounds and structural capacity of existing floors
- Maintaining patient and visitor safety during delivery








### Equipment Delivery - Solutions

- Coordinated delivery from Second Street SW.
- Street closure with City of Rochester and Mayo Transportation
- Coordinated with structural engineer for evaluation of floor system.






### Equipment Delivery/Assembly

• Component parts for Magnetically Shielding Room removed from boxes and thoughtfully placed according to location of assembly with limited space in built-out MEG suite.

Assembly of Magnetically Shielded Room:

• Tight existing conditions made assembly challenging.



### CONSTRUCTION ADMINISTRATION

Salon-style hair-wash sink added during construction:

- Either a salon-style sink or wipes are used by care team to clean metallic material from patient's hair before application of electrode cap. Metallic materials are common in hair care products and will distort MEG images.
- Resolve during design-phase to avoid construction phase floor slab demolition, sink supports, and routing of new waste and water lines.



## PROJECT PHOTOGRAPHY



Corridor SC3A, MEG Suite Entry





Before – Corridor SC3A



View Looking Back Towards Entry



After – Prep Room with Anesthesia Infrastructure and Salon Sink



After – Prep Room with Digitizing Computer, Electrode Cap and Digitizing Chair





MEG Tech Work Area and Magnetically Shielded Room









Open House – Magnetically Shielded Room Blessing



# PROJECT KEY TAKEAWAYS

- MEG does not use any magnets. The test uses very sensitive detectors to measure magnetic fields from the brain.
- Existing MEG Facilities site visits are helpful to the Proponents and Design Team.
- Vendor Design Guides provide minimum programmatic requirements. Discuss additional needs with the Proponent Team.
- Determine if MEG patients will be anesthetized and if inpatients will be tested in the MEG Lab. Both impact occupancy classification.
- 40% relative humidity is required for the MEG Lab.
- Consider the MEG and MSR equipment drop-off location and delivery path to project site.





QUESTIONS & ANSWERS

### THANK YOU!

#### QUESTIONS? CONTACT US

**ERIC STRICKLAND** 

Senior Healthcare Planner RSP Architects

eric.strickland@rsparch.com

BENJAMIN BRINKMANN, PH.D.

Professor of Neurology and Associate Professor of Biomedical Engineering Mayo Clinic

Brinkmann.Benjamin@mayo.edu

CHARLES ASAMOAH, P.E.

Project Manager
Department of Facilities
Project Services
Mayo Clinic

Asamoah.Charles@mayo.edu

**CRAIG NEUSER** 

Construction Manager Department of Facilities Project Services Mayo Clinic

Neuser.Craig@mayo.edu



